SANITARY AND TOWN PLANNING DIVISION.

Dated 7th December 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Sanitary and Town Planning Division, up to 4 P.M., on 2nd January 1930, for laying 9" main at Kolar. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 15th April 1930.

2. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

3. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for laying 9" main at Kolar, in default of which tenders will be rejected.

4. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

5. Within eight days of acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

6. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

7. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

8. In all matters of disputes not specially provided for and in all matters of dispute about rates, quantities, measurements and quality of work and in all disputes of any kind the decision of the Chief Engineer, will be final and legally binding.

Abstract of quantities.

No.	Particulars	Unit	Quantity
1	Earth work excavation and refilling with watering and tamping in ordinary soil and gravel and mooram.	C.yd.	2,250
2	Do do soft rock ...	,,	750
3	Removing hard rock by wedges	,,	500
4	Do by blasting	,,	50
5	Conveying from stores, laying and jointing 9" cast iron pipes 9' to 12' long with cuts, collars, etc., complete with cement.	Joint	800
6	Do do with lead ...	,,	100
7	Do do 6" pipes with cement ...	,,	6
8	Forming footpath on pipe line with available earth ...	Sq.yd.	6,000
9	Surki concrete	C.ft.	180
10	Burnt brick in surki mortar	,,	560
11	Burnt stone slabs one line dressed and fixed	Sq.ft.	220
12	Surki plastering	Sq.	4·5
13	Fixing valve cistern covers after drilling holes in slabs ..	No.	10
14	Removing and resetting slabs covering drains, etc. ...	Sq.ft.	50
15	Turfing	Sq.yd.	20
16	Rough stone revetment with new stones	C.yd.	10

H. F. MARKER,
Executive Engineer.

OFFICE OF THE EXECUTIVE ENGINEER, No. III, IRWIN CANAL DIVISION

Notification.

An old tent will be auctioned at 4 P.M. on the 15th December 1929, at Bevinkuppe Headquarters of No. III, Irwin Canal Division, 2 miles north of French Rocks Town.

The tent will be knocked down to the highest bidder who should pay the amount of bid immediately.

M. V. KRISHNASWAMY IYENGAR,
For *Executive Engineer.*